

Date: Wednesday, 13/05/2009 1:42:23 PM  
 User: Julie Dawson

## Process Sheet

<b>Customer</b> : CU-DAR001 Dart Helicopters Services	<b>Drawing Name</b> : BASKET BASE ASSEMBLY (350)
<b>Job Number</b> : 47941C	
<b>Estimate Number</b> : 10189	
<b>P.O. Number</b> :	<b>Part Number</b> : D2221
<b>This Issue</b> : 13/05/2009 <b>S.O. No.</b> :	<b>Drawing Number</b> : D2221 REV H
<b>Prsht Rev.</b> : NC	<b>Project Number</b> : N/A
<b>First Issue</b> : / / <b>Type</b> : LARGE FAB ASSY	<b>Drawing Revision</b> : H
<b>Previous Run</b> : 46730A	<b>Material</b> :
<b>Written By</b> :	<b>Due Date</b> : 22/05/2009 <b>Qty:</b> 1 <b>Um:</b> Each
<b>Checked &amp; Approved By</b> : <u>JUD 09.05.13</u>	
<b>Comment</b> : Est Rev:J 05.09.02 Added D3442-1 KJ/JLM Est Rev:K 08-08-29 revG as per dwg DD verified by:EC Est Rev:L 08-09-24 plug holes prior to powder coat DD verified by:EC Est Rev:M 08-12-02 revH as per dwg DD verified by:	

## Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
---------	-----------------------	---------------

1.0	D22211	Rib
-----	--------	-----



**Comment:** Qty.: 1.0000 Each(s)/Unit Total : 1.0000 Each(s)  
 Rib  
 batch: B 45938 → 1x SM 09/05/19

2.0	D22215	Rib
-----	--------	-----



**Comment:** Qty.: 2.0000 Each(s)/Unit Total : 2.0000 Each(s)  
 Rib  
 batch: B 46365 → 2x SM 09/05/19

3.0	D22217	Rib
-----	--------	-----



**Comment:** Qty.: 1.0000 Each(s)/Unit Total : 1.0000 Each(s)  
 Rib  
 batch: B 46769 → 1x SM 09/05/19

4.0	D22323	Basket Hinge
-----	--------	--------------



**Comment:** Qty.: 2.0000 Each(s)/Unit Total : 2.0000 Each(s)  
 Basket Hinge  
 batch: B 46626 → 1 B 46822 → 1x SM 09/05/19

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

Resolution: \_\_\_\_\_ Disposition: \_\_\_\_\_ QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Wednesday, 13/05/2009 1:42:23 PM  
User: Julie Dawson

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: BASKET BASE ASSEMBLY (350)

Job Number: 47941C

Part Number: D2221

Job Number:



Seq. #: Machine Or Operation: Description :

5.0

D22351

Basket Rib



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)

Basket Rib

batch: ~~B46623~~ <sup>B46625</sup> <sup>41836</sup> <sup>1x</sup>

*dy 09/05/19*

6.0

D2581

Mounting Bracket



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)

Mounting Bracket

batch: ~~B46086~~ <sup>B46086</sup> <sup>2x</sup>

*dy 09/05/19*

7.0

D34421

Shim



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)

Shim

batch: ~~B46764~~ <sup>B46764</sup> <sup>1x</sup> ~~B46809~~ <sup>B46809</sup> <sup>1x</sup>

*dy 09/05/19*

8.0

D3825041

Rib Assembly (Basket End)



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)

Rib Assembly (Basket End)

batch: ~~B46773~~ <sup>B46773</sup>

*dy 09/05/19*

9.0

D3826041

Rib / Gusset Assembly



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)

Rib / Gusset Assembly

batch: ~~B46810~~ <sup>B46810</sup>

*dy 09/05/19*

10.0

D3827041

Rib Assembly (Inboard)



Comment: Qty.: 1.0000 Each(s)/Unit Total: 1.0000 Each(s)

Rib Assembly (Inboard)

batch: ~~B46476~~ <sup>B46476</sup> <sup>1x</sup>

*dy 09/05/19*

11.0

D38331

Mesh (Base End Face)



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)

Mesh (Base End Face)

batch: ~~B46665~~ <sup>B46665</sup> <sup>2x</sup>

*dy 09/05/20*

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

Resolution: \_\_\_\_\_ Disposition: \_\_\_\_\_ QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries

Date: Wednesday, 13/05/2009 1:42:24 PM  
User: Julie Dawson

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: BASKET BASE ASSEMBLY (350)

Job Number: 47941C

Part Number: D2221

Job Number:



Seq. #:

Machine Or Operation:

Description :

12.0

D38321

Mesh (Base)



Comment: Qty.: 1.0000 Each(s)/Unit Total : 1.0000 Each(s)

Mesh (Base)

batch: B 46774

SL 09/05/20

13.0

LARGE FAB 1

LARGE FABRICATION RESOURCE 1



Comment: LARGE FABRICATION RESOURCE 1

1- assemble all ribs and both D2581 in DT9444 jig, weld as per dwg D2221

2- remove basket from jig and weld D3442-1 shims and D2232-3 hinges as per dwg D2221

3- tack weld mesh on basket as per dwg D2221

A/R ER316 S.S. Rod Batch: ~~154665~~  
M109213

SL 09/05/21 (X)

14.0

QC9

VISUAL WELDING INSPECTION



Comment: VISUAL WELDING INSPECTION

Cpl 09-05-22

15.0

QC6

DIMENSIONAL CHECK



Comment: DIMENSIONAL CHECK

S 09/05/25 (X)

16.0

POWDER COATING

POWDER COATING



Comment: POWDER COATING

M111472  
Pressure wash MD 09/05/25

1- Plug holes prior to powder coating

2-Powder Coat White Gloss (Ref: 4.3.5.1) as per QSI 005 4.3

1ST COAT:

START TIME: 1:50pm

OVEN TEMPERATURE: 400°F

FINISH TIME: 2:20pm

\*\*\*\*\* 2nd coat if necessary \*\*\*\*\*

2ND COAT:

START TIME: 2:30pm

OVEN TEMPERATURE: 400°F

FINISH TIME: 3:00pm

SL 09-05-25 (X)

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

Resolution: \_\_\_\_\_ Disposition: \_\_\_\_\_ QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries

Date: Wednesday, 13/05/2009 1:42:24 PM  
User: Julie Dawson

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: BASKET BASE ASSEMBLY (350)

Job Number: 47941C

Part Number: D2221

Job Number:



Seq. #:

Machine Or Operation:

Description :

17.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT/CHEMICAL CONVERSION

umol/K 09/05/2009 (X)

18.0

QC21

FINAL INSPECTION/W/O RELEASE



Comment: FINAL INSPECTION/W/O RELEASE

09/05/28 JF

Job Completion



MF 09-05-27

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector


Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

Resolution: \_\_\_\_\_ Disposition: \_\_\_\_\_ QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries





**D2221 BASKET BASE ASSEMBLY (AS350)**  
(MESH SHOWN LOCALLY FOR CLARITY)

SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 479412



**NOTES:**

- 1) MATERIAL: N/A
- 2) FINISH: POWDER COAT GLOSS WHITE (4.3.5.2) PER DART QSI 005 4.3
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: N/A
- 8) WEIGHT: 42.00 lbs APPROX
- 9) MASK ALL HOLES PRIOR TO POWDER COATING

ITEM	QTY	P/N	DESCRIPTION
1	X	D2221	BASKET BASE ASSEMBLY (AS350)
2	1	D2221-1	RIB
3	2	D2221-5	RIB
4	1	D2221-7	RIB
5	2	D2232-3	BASKET HINGE
6	2	D2235-1	RIB
7	2	D2581	MOUNTING BRACKET
8	2	D3442-1	SHIM
9	2	D3825-041	RIB ASSY (BASKET END)
10	2	D3826-041	RIB/GUSSET ASSY
11	1	D3827-041	RIB ASSY (INBOARD)
12	2	D3833-1	MESH, BASE END FACE
13	1	D3832-1	MESH (BASE)

RELEASED  
08/11/18

H	REVISED PARTS LIST AND ADDED "ITEM" COLUMN TO PARTS LIST (ZN D3-1); REVISED SECTIONS A-A, B-B AND C-C (ZN C6-3, C2-3 AND A6-3); REVISED DETAIL D (ZN B7-4); ADDED DETAIL E (ZN A6-4); ADDED SECTION F-F (ZN B2-4); ADDED DWG DETAILS FOR D2221-1/-5/-7 (SHEET 5); TOL REVISED TO 2 DEC PLACES (ZN D8-3 AND ZN B4-3); D3825-041 REPLACES D2221-3/D2327-3; D3826-041 REPLACES D2235-1/D2325; D3827-041 REPLACES D2221-1 ON INBOARD SIDE; ADDED D3832-1 AND D3833-1. REASON: SATISFY "LEAN MANUFACTURING" PROGRAM.	MB	08.09.18
G	MATERIAL FOR -1, -3, -5 & -7 WAS 0.060 WALL; TOLERANCE FOR 98.00 DIM WAS +/0.01 AND 56.00 DIM WAS REF (ZN B5-2); 19.62 DIM WAS "HARD" DIMENSION IS NOW "REF" (ZN B4-2); NOTE 5 TRANSFERRED FROM SHT 1 TO SHT 2; SHT 2 MESH MATERIAL UPDATED; DRAWING TRANSFERRED TO "B" FORMAT	AJS	08.06.16
F	ADD SHIM UNDER HINGE; ADD HOLES FOR SPLIT LID BASKET	PH	05.06.07
E	CHANGE HINGE	CP	01.04.19
D	CHANGE LATCH	BW	96.06.21
C	SEPARATE BASKET AND LID	KH	95.11.21
REV.	DESCRIPTION	BY	DATE
DESIGN	BW	<b>DART AEROSPACE LTD</b> HAWKESBURY, ONTARIO, CANADA	
DRAWN	BW		
CHECKED	JS	DRAWING NO.	REV. H
MFG. APPR.	JS	D2221	SHEET 1 OF 5
APPROVED	JS	TITLE	SCALE
DE APPR.	JS	BASKET BASE ASSEMBLY (350)	NTS
DATE	08.09.18	<small>COPYRIGHT © 1994 BY DART AEROSPACE LTD  THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD</small>	




**D2221 BASKET BASE ASSEMBLY (350)**  
(MESH SHOWN LOCALLY FOR CLARITY)

**RELEASED**  
06/11/18 NAD

SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER NO. 170412

DESIGN	BW	<b>DART AEROSPACE LTD</b>	REV. H
DRAWN		HAWKESBURY, ONTARIO, CANADA	
CHECKED		DRAWING NO. <b>D2221</b>	SHEET 2 OF 5
MFG. APPR.		TITLE	SCALE
APPROVED		<b>BASKET BASE ASSEMBLY (350)</b>	NTS
DE APPR.		COPYRIGHT © 1994 BY DART AEROSPACE LTD	
DATE	08.09.18	THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD	



DESIGN	BW	<b>DART AEROSPACE LTD</b>	
DRAWN		HAWKESBURY, ONTARIO, CANADA	
CHECKED	435	DRAWING NO.	REV. H
MFG. APPR.		D2221	SHEET 3 OF 5
APPROVED	AN	TITLE	SCALE
DE APPR.		<b>BASKET BASE ASSEMBLY (350) NTS</b>	
DATE	08.09.18	COPYRIGHT © 1994 BY DART AEROSPACE LTD	
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL, AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.			


8 7 6 5 4 3 2 1

D


C

B


A



**DETAIL D**  
SCALE 4X D2-2



**DETAIL E**  
SCALE 4X C6-2






**SECTION F-F**  
SCALE 4X D7-2

**RELEASED**  
08/11/18


SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 12941C

DESIGN	BW	<b>DART AEROSPACE LTD</b>	
DRAWN		HAWKESBURY, ONTARIO, CANADA	
CHECKED	<i>[Signature]</i>	DRAWING NO. <b>D2221</b>	REV. H
MFG. APPR.	<i>[Signature]</i>		SHEET 4 OF 5
APPROVED	<i>[Signature]</i>	TITLE	SCALE
DE APPR.	<i>[Signature]</i>	<b>BASKET BASE ASSEMBLY (350)</b>	NTS
DATE	<b>08.09.18</b>	COPYRIGHT © 1994 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD	

8 7 6 5 4 3 2 1



**D2221-1 RIB**



**D2221-5/-7 RIB**

**RELEASED**  
08/11/18

**NOTES:**

- 1) MATERIAL: AISI 304/316 STAINLESS STEEL SQUARE TUBE, 0.75 X 0.75 X 0.065 WALL  
REF. DART SPEC. M304TS0.750W0.065
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: N/A
- 8) WEIGHT: D2221-1 = 4.57 lbs; D2221-5 = 0.90 lbs; D2221-7 2.65 = lbs

DESIGN	BW	<b>DART AEROSPACE LTD</b>	
DRAWN		HAWKESBURY, ONTARIO, CANADA	
CHECKED	ASD	DRAWING NO.	REV. H
MFG. APPR.	MD	D2221	SHEET 5 OF 5
APPROVED	W	TITLE	SCALE
DE APPR.	W	<b>BASKET BASE ASSEMBLY (350)</b> NTS	
DATE	08.09.18	COPYRIGHT © 1994 BY DART AEROSPACE LTD	
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.			

NO. 27041C  
WORK ORDER  
WITHOUT NOTICE  
UNCONTROLLED COPY  
ENGINEERING  
RETURN TO  
SHOP COPY